

SECOND FLOOR

The contractor is required to check all dimensions, levels and relevant site conditions before any construction takes place.
DO NOT SCALE FROM THIS DRAWING.

STATUS - CONSTRUCTION

NOTES

1. Levels indicated originate from those on most recent survey undertaken by PAJ Engineering Surveys of lower ground and ground floor levels. These levels are not OS levels or consistent with those on record information. Upper floor levels have been amended to co-ordinate with those at lower floors.
2. Existing walls indicated by solid hatching.
3. New doors are denoted thus unless noted otherwise.
4. Unless noted existing walls to be lined with plasterboard on adhesive as NBS Clause K10/185. Lining of window reveals to be carefully co-ordinated with refurbishment of windows.
5. New Blockwork wall linings: Plasterboard on studs - NBS K10/185 generally. Refer to this area in table.


IRE COMPARTMENTS (60 MINS)

Indicated by line thus: All penetrations to be firestopped as per NBS P12/130 & 131. Ducts to have fire dampers on line of Compartment. Refer to M&E Engineers Detail.

Wall Type Key

- Existing Solid Wall
- New 140mm Blockwork (NBS F10/351-352)
 - New 70mm Metal Stud Wall (NBS K10/126,126,127)

H	Construction issue	11.07.07
G	Notes added re floor grates in plan; note added re window cleaning system; CDR access doors amended to penny tanning doors	03.05.07
F	Notes added re window cleaning suite	07.03.07
E	Fire Comp. indicated. Notes amended	09.02.07
D	Included in list of existing section notes. Building Warrant Book	22.12.06
C	Drainage notes added; sash window note added	06.11.06
B	W/C layouts updated; door sets added; cavity transfer indicated	16.10.06
A	W/C layouts updated; tenant's store omitted	21.09.06




empire house 131 west gile street glasgow G1 2RX
tel 0141 332 6804 fax 0141 333 0813
projects@gjalodge.co.uk
www.gjalodge.co.uk

CLIENT
ROYAL INSURANCE UK LTD

PROJECT
206 ST. VINCENT STREET
GLASGOW

DRAWING SECOND FLOOR PLAN AS PROPOSED	
DATE JULY 06	DRAWN BY BT
SCALE 1:100@A1	CHECKED BY JCP
JOB NO. 2099	DRAWING NO. 112
REVISION	REVISION H



The contractor is advised to check all dimensions, levels and relevant life conditions before any construction takes place.
DO NOT SCALE FROM THE DRAWING.

STATUS - CONSTRUCTION

- NOTES
- Levels indicated originate from those on most recent survey undertaken by SML Engineering Services of lower ground and ground floor levels. These levels are not CG levels or consistent with those on record information. Upper floor levels have been amended to co-ordinate with those of lower floors.
 - Existing walls indicated by solid hatching.
 - New doors/detents denoted thus unless noted otherwise.
 - Unless noted existing walls to be lined with plasterboard on adhesive as NBS Clause K10/136, spring of window reveals to be complete, co-ordinated with replacement of windows.
 - New Backwork wall linings: Plasterboard on studs - NBS K10/155 generally. Refer to lined areas in tables.

FIRE COMPARTMENTS (60 MINS)

Indicated by line thus: ---
All penetrations to be firestopped as per NBS P12/130 & 131. Ducts to have fire closures on line of Compartment. Refer to V&E Engineers Details.

Wall Type Key

- Existing Solid Wall
- New 140mm Backwork (NBS F10/351-352)
- New 70mm Metal Stud Wall (NBS K10/125,126,127)

H	Construction Issue: extent of new cladding to rear of mansard raised to reflect client's comments: Backwork ceiling out of context	11.07.07
G	External paved area extended to north east. Floor system updated to ANU. Notes address floor grates in gaps. Note added re window/docking equipment. Office entrance door moved to penny flooring door. New block wall indicated to remain in place.	06.05.07
F	Notes address re: full arrest system.	07.03.07
E	Fire Comp. indicated. Notes amended.	09.02.07
D	Indicative positions of existing not faces added. Building Workman/Doc.	22.12.06
C	Drainage notes added.	08.11.06
B	WC layouts updated above re:ts added, cavity blocked in places.	18.10.06
A	WC layout updated to meet N's store complied.	21.09.06



empire house 131 west Nile street glasgow G1 2PX
tel 0141 332 6804 fax 0141 333 0813
projects@go.lodge.co.uk
www.go.lodge.co.uk

CLIENT
ROYAL INSURANCE UK LTD

PROJECT
206 ST. VINCENT STREET
GLASGOW


DRAWING
THIRD FLOOR PLAN
AS PROPOSED

DATE	DRAWN BY
JULY 06	BT

SCALE	CHECKED BY
1:100@A1	JCP

JOB NO.	DRAWING NO.	REVISION
2099	113	H

THIRD FLOOR



FOURTH FLOOR

The contractor is cautioned to check all dimensions, levels and relevant site conditions before any construction takes place.
DO NOT SCALE FROM THIS DRAWING.

STATUS - CONSTRUCTION

- NOTES
- Levels indicated originate from those on most recent survey undertaken by PGL Engineering Surveys of lower ground and ground floor levels. These levels are not CG levels or consistent with those on record information. Upper floor levels have been amended to co-ordinate with those of lower floors.
 - Existing walls indicated by solid hatching.
 - Existing walls indicated by solid hatching.
 - Unless noted existing walls to be lined with plasterboard on adhesive as NBS Clause K10/186. Lining of window reveals to be carefully co-ordinated with refurbishment of windows.
 - New Blockwork wall/joints: Plasterboard on dates - NBS K10/183 generally. Refer to tiled areas in details.

FIRE COMPARTMENTS (60 mins)
Indicated by line thus: All partitions to be firestopped as per NBS P12/130 & 131. Ducts to have fire dampers on line of Compartment. Refer to M&E Engineers Detail.

Wall Type Key
Existing Solid Wall
New 140mm Blockwork (NBS F10/351.352)
 New 50mm Metal Stud Wall (NBS K10/125.126.127)

G	Construction notes: Blockwork sitting out outside.	11.07.07
F	Notes update re floor grating in floor, note added re window cleaning system. Office access doors amended to permit forming door-to-door block wall access to female toilet.	08.05.07
E	Fire Comp. indicated. Notes amended.	09.02.07
D	Indicative locations of existing cold mains noted. Building Warrant filed.	22.12.06
C	Drawings notes added.	04.11.06
B	WC layouts updated: door refs added, ceiling beams indicated.	14.10.06
A	WC layouts updated: tenant's store confirmed.	21.09.06

g.lodge architects
empire house 131 west nile street glasgow G1 2RX
tel 0141 332 6804 fax 0141 333 0813
projects@glodge.co.uk
www.glodge.co.uk

CLIENT
ROYAL INSURANCE UK LTD

PROJECT
206 ST. VINCENT STREET
GLASGOW

DRAWING
FOURTH FLOOR PLAN
AS PROPOSED

DATE	DRAWN BY	
JULY 06	BT	
SCALE	CHECKED BY	
1:100@A1	JCP	
JOB NO.	DRAWING NO.	REVISION
2099	114	G